



▶▶ HOLD DOWN STRAP LOCATION * FITTINGS CANNOT BE INSTALLED IN THESE LOCATIONS

| FITTING SCHEDULE | | DESCRIPTION | | NOTES | | DRAWING NUMBER: | | REVISION: | |
|------------------|----------------|-------------|--|--|---------------------------|------------------|----|-----------|---|
| DOM 2 | 100NB | SOCKET | 100NB BSP SOCKET | - Tie-Down Straps to suit this tank are part no. | | | | | |
| 5 | 100NB | SOCKET | 100NB BSP SOCKET | - Dedmen to suit this tank are part no. | | | | | |
| 3-4 | 100NB | MONITOR | INTERSTICE MONITOR SOCKET | | | | | | |
| 1-2 | 600NB | MANHOLE | MANHOLE c/w COVER & 5 x 100NB SOCKETS, RISER & LID | - UNO, all sockets are BSP and are c/w striker plates under. | | | | | |
| FLAT No. | SIZE | ITEM | DESCRIPTION | Notes | No | Revision Details | By | Date | |
| DRAWN: V.B.B. | App. Weight: | 930 kg | Construction | Type | Compartment Configuration | DRAWING NUMBER: | | | |
| DATE: 23/07/01 | App. Capacity: | 15,444 L | DOUBLE WALL | TYPE 15 | SINGLE | FD 015000-000 | | | A |

The contractor shall provide Fibreglass Reinforced Plastic (FRP) underground storage tanks as illustrated. Sizes & fittings shall be as noted. The tanks shall be "Century-Cast" tanks as manufactured by Fibretank Systems. Tanks shall be tested & installed as per current specifications and instructions.

All dimensions in millimetres. All dimensions are nominal unless a manufacturing tolerance has been specified.

THIS DRAWING & THE INFORMATION CONTAINED HEREIN IS THE PROPERTY OF FIBRE TANK SYSTEMS AND STRICTLY CONFIDENTIAL & MUST NOT BE USED OR DISCLOSED WITHOUT WRITTEN CONSENT OF FIBRETANK SYSTEMS PTY LIMITED

FIBRETANK SYSTEMS Pty Limited
 PO BOX 102
 CARRINGTON., NSW 2294
 Ph:(02)4961-2745 Fax:(02)4962-2812