



TANK 1 VOLUME = 19,638 L APPROX TANK 2 VOLUME = 32,729 L APPROX TANK 3 VOLUME = 19,638 L APPROX

▶▶ HOLD DOWN STRAP LOCATION * FITTINGS CANNOT BE INSTALLED IN THESE LOCATIONS

FITTING SCHEDULE		FIBRETANK SYSTEM STD	
DOME	100NB	SOCKET	100NB BSP SOCKET
16	600NB	MANHOLE	MANHOLE c/w COVER & 5 x 100NB SOCKETS, RISER & LID
13-14	100NB	MONITOR	INTERSTICE MONITOR SOCKET
10-11	600NB	MANHOLE	MANHOLE c/w COVER & 5 x 100NB SOCKETS, RISER & LID
8	100NB	SOCKET	100NB BSP SOCKET
7	100NB	SOCKET	100NB BSP SOCKET
4-5	100NB	MONITOR	INTERSTICE MONITOR SOCKET
2	600NB	MANHOLE	MANHOLE c/w COVER & 5 x 100NB SOCKETS, RISER & LID
DOME	100NB	SOCKET	100NB BSP SOCKET
FLAT No.	SIZE	ITEM	DESCRIPTION

DRAWN: V.B.B. App. Weight: 3,246 kg Construction Type Type 70 Notes A Original Issue Revision Details By Date

DATE: 22-10-03 App. Capacity: 72,005 L DOUBLE WALL TRIPLE 20/30/20 DRAWING NUMBER: FR 070000-001 REVISION: A

The contractor shall provide Fibreglass Reinforced Plastic (FRP) underground storage tanks as illustrated. Sizes & fittings shall be as noted. The tanks shall be "Century-Cast" tanks as manufactured by Fibretank Systems. Tanks shall be tested & installed as per current specifications and instructions.

All dimensions in millimetres. All dimensions are nominal unless a manufacturing tolerance has been specified.

THIS DRAWING & THE INFORMATION CONTAINED HEREIN IS THE PROPERTY OF FIBRE TANK SYSTEMS AND STRICTLY CONFIDENTIAL & MUST NOT BE USED OR DISCLOSED WITHOUT WRITTEN CONSENT OF FIBRETANK SYSTEMS PTY LIMITED

FIBRETANK SYSTEMS Pty Limited
PO BOX 102
CARRINGTON, NSW 2294
Ph:(02)4961-2745 Fax:(02)4962-2812