



◀◀ HOLD DOWN STRAP LOCATION

\* FITTINGS CANNOT BE INSTALLED IN THESE LOCATIONS

| FITTING SCHEDULE  |                |          |   | FIBRETANK SYSTEMS Pty Limited |   |                 |                  | No   | Revision Details | By   | Date |
|---|----------------|----------|---|-------------------------------|---|-----------------|------------------|--|------------------|------|------|
| 20  | 100NB          | SOCKET   | 100NB BSP SOCKET  |                               |   |                 |                  |  |                  |      |      |
| 18-19   | 100NB          | MONITOR  | INTERSTICE MONITOR SOCKET   |                               |   |                 |                  |  |                  |      |      |
| 11  | 100NB          | SOCKET   | 100NB BSP SOCKET  |                               |   |                 |                  |  |                  |      |      |
| 4-5   | 100NB          | MONITOR  | INTERSTICE MONITOR SOCKET   |                               |   |                 |                  |  |                  |      |      |
| 2-3   | 600NB          | MANHOLE  | MANHOLE c/w COVER & 5 x 100NB SOCKETS, RISER & LID  |                               |   |                 |                  |  |                  |      |      |
| FLAT No.  | SIZE           | ITEM     | DESCRIPTION   | Notes                         | DRAWING NUMBER:   |                 | Revision Details |  | By               | Date |      |
| DRAWN: V.B.B.   | App. Weight:   | 3,970 kg | Construction  | Type                          | Compartment Configuration   | DRAWING NUMBER: |                  | REVISION:  |                  |      |      |
| DATE: 24-07-01  | App. Capacity: | 81,824 L | DOUBLE WALL   | TYPE 80                       | SINGLE  | FD 080000-000   |                  | A  |                  |      |      |
| <p>The contractor shall provide Fibreglass Reinforced Plastic (FRP) underground storage tanks as illustrated. Sizes &amp; fittings shall be as noted. The tanks shall be "Century-Cast" tanks as manufactured by Fibretank Systems. Tanks shall be tested &amp; installed as per current specifications and instructions.</p> |                |          | <p>All dimensions in millimetres. All dimensions are nominal unless a manufacturing tolerance has been specified.</p> |                               | <p>THIS DRAWING &amp; THE INFORMATION CONTAINED HEREIN IS THE PROPERTY OF FIBRE TANK SYSTEMS AND STRICTLY CONFIDENTIAL &amp; MUST NOT BE USED OR DISCLOSED WITHOUT WRITTEN CONSENT OF FIBRETANK SYSTEMS PTY LIMITED</p> |                 |                  | <p>FIBRETANK SYSTEMS Pty Limited<br/>PO BOX 102<br/>CARRINGTON., NSW 2294<br/>Ph:(02)4961-2745 Fax:(02)4962-2812</p> |                  |      |      |