



**NOTE:**

- 1: VACUUM ON INTERSTITIAL SPACE IS FACTORY SET & GAUGE SET
- 2: INSTALLATION AS PER GLASTEEL II INSTALLATION INSTRUCTIONS & APPLICABLE CODES
- 3: VESSEL IDENTIFICATION No. & MANUFACTURE DATE ARE LAMINATED TO TOP OF VESSEL
- 4: VESSEL MANUFACTURED TO AS1692
- 5: PLASTIC LIFTING LUG COVERS SUPPLIED WITH VESSEL
- 6: HOLD DOWN STRAPS POSITION ARE TO BE MARKED ON VESSEL DURING MANUFACTURING
- 7: ALL SOCKETS TO BE CLEANED AND FITTED WITH PLASTIC DUST CAPS
- 8: 6mm STRIKER PLATES TO BE FITTED UNDER ALL OPENINGS
- 9: ALL WELDS AS PER AS1554.1-GP (N.D.T. - VISUAL)
- 10: VOLUME = 45,860 L (APPROX)
- 11: WEIGHT OF TANK = 4,130 kg (APPROX)

S1	HOLD DOWN STRAPS	4	015001
	VACUUM MONITOR GAUGE	1	006137, 017111, 017160
	LIFTING LUG COVERS	2	015071
	DIPSTICK T45	1	SUB1070
	<b>ACCESSORIES</b>	<b>QTY</b>	<b>PART / SUB ASSM No.</b>

10	1	STRIKER PLATE	SUB1047
9	2	LIFTING LUG - 5 TONNE C/W DOUBLER PAD	SUB1076
8	2	END $\phi 2190$ I.D x 5 PLATE	SUB1004
7	4	SHELL $\phi 2190$ I.D x 5 PLATE x 3000 LONG	SUB1036
6	1	50NB (NPT) MONITOR SOCKET C/W INTERNAL PIPE	SUB1081
5	1	FRP COLLAR	SUB1028
4	1	600NB MANWAY C/W 5 x 100NB SOCKETS	SUB1095
3	1	100NB FILL SOCKET C/W PIPE	SUB1056
2	1	80NB DIP SOCKET C/W PIPE	SUB1051
1	1	100NB PHOENIX FLANGE	006395

ITEM	QTY	DESCRIPTION	PART / SUB ASSM No.
		<b>FIBRETANK SYSTEMS PTY LIMITED</b>	<b>PO BOX 102 CARRINGTON N.S.W. 2294 PHONE (02) 4961-2745 FAX: (02) 4962-2812</b>
<b>TITLE:</b> GENERAL ARRANGEMENT T45 GLASTEEL II U/G STORAGE VESSEL			<b>VESSEL CLASS</b> N/A
<b>ESTIMATE NUMBER:</b> N/A		<b>DRAWING NUMBER:</b> JW 045000-006	
<b>JOB No:</b>		<b>SHEET:</b> 1 of 1	<b>REVISION:</b> A

No.	REVISION DETAILS	BY	DATE	CLIENT:
F				TANK SOLUTIONS for PETRO STANTHORPE
E				DRAWN: V.B.B. DATE: 17-05-02
D				CHECKED: DATE:
C				APPROVED: DATE:
B				ORDER No: No OFF: ONE (1)
A	ORIGINAL ISSUE	0	0	SCALE: N.T.S. CAD REF: JW-GST-SC-P

Dimension in millimetres  
All tolerancing to be to the applicable design code of manufacture, and/or client requirement.